

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE NW SW

SEC. 7 TWP. 10 RGE. 19 *W*

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Dunlap

Operator C & G Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3816 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement - 5 1/2" at 3797' with
100 sax cement behind.

Filled with chat to 3785' set 4 sax cement with dump bailer,
pulled 3160' 5 1/2", filled with mud to 250', set rock and 15
sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

District Conservation Agent

Date 9-15-52

RECEIVED
STATE CORPORATION COMMISSION
9-18-52
SEP 18 1952
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 7 T 10 R 19
BOOK PAGE 48 LINE 23