

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SW SW

SEC. 7 TWP. 10 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Dunlap 107 Aule Bldg.

Operator C & G Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3788 Feet.

Plugging Contractor Globe Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement - 5 1/2" at 3783 8 perforated at 1180' and squeezed with cement from 1180' to 0'. No pipe recovery. Pumped hole full commercial mud (40 sax Gel) - pumped cementing plug followed by 40 sax cement - top of cement found at 690' - filled hole with heavy rotary mud 690' to 40', set rock bridge at 40' and filled to 0' with cement.

Edward Lee
District Conservation Agent

Date 4-19-57

RECEIVED
STATE CORPORATION COMMISSION
4-25-57
APR 25 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 7 T. 10 R. 19W
BOOK PAGE 8 LINE 39