

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01149-00-01  
Spot: NW SE SW Sec/Twnshp/Rge: 4-10S-19W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: ONDRASEK OWWO Well Number: 3  
County: ROOKS Total Vertical Depth: 3720 feet

Operator License No.: 30717  
Operator Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 372  
HAYS, KS 67601

Conductor Pipe: Size feet:  
Surface Casing: Size 8.62 feet: 216  
Production: Size 5.5 feet: 3717 **120.90**  
Liner: Size 4.5 feet: 3415

Well Type: OIL UIC Docket No: Date/Time to Plug: 9/20/00 10:00:00 AM  
Plug Co. License No.: 30717 Plug Co. Name: DOWNING-NELSON OIL CO INC  
Proposal Rcvd. from: RON NELSON Company: DOWNING-NELSON OIL CO INC Phone: (785) 628-3449

Proposed Plugging Method: According to KCC Rules & Regulations.  
Ordered 275 sxs cement - 600# hulls.  
Perforate at 900' - 1575' - 2260'.  
Plug thru casing.

Plugging Proposal Received By: ROGER MOSES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/20/2000 11:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:  
8 5/8" S.P. at 216'. 5 1/2" casing at 3717'. 4 1/2" liner at 3415'.  
4 1/2" liner circulated with cement.  
Tied to 4 1/2" liner - pumped 40 sxs cement with 300# hulls - pumped 12 sxs gel followed with 100 sxs cement. Pressured to Max. P.S.I. 1000#.  
S.I.P. 300#. Annulus full of cement.  
Total of 140 sxs 60/40 pozmix - 10% gel - 500# hull - 12 sxs gel.

Remarks: ALLIED CEMENTING COMPANY. STEWART TANK - WATER.

Plugged through: CSG

District: 04

Signed Roger L. Moses  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION

10-3-00  
OCT 3 2000

INVOICED

DATE 10/4/00

INV. NO. 2001060795

CONSERVATION DIVISION  
Wichita, Kansas 67202

SEP 22 2000

BLACK GOLD OIL COMPANY  
 P.O. BOX 26  
 HAYS, KS 67601  
 CONTR SUPERIOR WELL SERVICE CTY ROOKS  
 GEOL \_\_\_\_\_ FIELD LYND  
 E 2193 CM 8/28/80 CARD ISSUED 1/29/81 IP P 15 BOPD & WTR  
 LANS 3579-3583

4-10-19W  
 NW SE SW

+	+
+	+

NOT ASSIGNED

API	TOPS	DEPTH	DAYUM
ANH	1559	+ 634	
HEEB	3373	-1180	
LANS	3409	-1216	
CONG	3706	-1513	
ARB	3716	-1523	
TD	3720	-1527	

OLD INFO: OPERATOR WAS K&E DRLG &  
 STABLEFORD #3ONDRASEK, SPD NA, SET  
 8" 216, 5" 3717, COMPLETED AS 200 BOPD  
 1/8/54

CO 3720: SWB 16 BOPH

NEW INFO: RE-ENTERED 8/23/80, WSH  
 DWN TO OTD, TIED INTO OLD PIPE, MICT -  
 CO, PF 3579-3583, AC 2000 GAL, POP,  
 P 15 BOPD & WTR

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS