

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03010-00-01  
Spot: CNWNESW Sec/Twnshp/Rge: 4-10S-19W  
2310 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: ONDRASEK Well Number: 2  
County: ROOKS Total Vertical Depth: 3702 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 372  
HAYS, KS 67601

Conductor Pipe Size: 0 feet: 0  
Production Casing Size: 4.5 feet: 1269  
Surface Casing Size: 8.625 feet: 216 150 SX CMT  
*8120.32 washdown*  
*PT KCC*

Well Type: SWD UIC Docket No: D20017.0 Date/Time to Plug: 03/26/2003 10:00 AM  
Plug Co. License No.: 30717 Plug Co. Name: DOWNING-NELSON OIL CO INC  
Proposal Rcvd. from: RON NELSON Company: DOWNING-NELSON OIL CO INC Phone: (785) 628-3449

Proposed Plugging Method: According to KCC Rules & Regulations.  
Ordered 100 sxs cement and 500# hulls.  
Perfs at 950' and 1650'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/26/2003 11:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 216' w/150 sxs cement. 4 1/2" casing at 1269' w/360 sxs cement.  
Tied to 4 1/2" casing and squeezed 100 sxs cement and 500# hulls.  
Pumped at 500# the duration of plugging to final Max. P.S.I. 1000#. S I.P. 1000#.  
Tied to 8 5/8" x 4 1/2" annulus - pressured up immediately - took no cement.  
Total of 100 sxs 60/40 pozmix - 10% gel and 500# hulls.

RECEIVED  
KANSAS CORPORATION COMMISSION  
4-2-03  
APR 02 2003  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: CSG

District: 04

Signed

*Roger J Moses*  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-3-03

REV. NO. 2003061372

MAR 28 2003

