

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00728-00-01
Spot: SE NE SW Sec/Twnshp/Rge: 4-10S-19W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: ONDRASEK OWWO Well Number: 1-A
County: ROOKS Total Vertical Depth: 3694 feet

Operator License No.: 30717
Operator Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 215
Production: Size 5.5 feet: 3690
Liner: Size 4.5 feet: 3692 *120.06*

Well Type: OIL UIC Docket No: Date/Time to Plug: 9/20/00 9:00:00 AM
Plug Co. License No.: 30717 Plug Co. Name: DOWNING-NELSON OIL CO INC
Proposal Rcvd. from: RON NELSON Company: DOWNING-NELSON OIL CO INC Phone: (785) 628-3449

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 300 sxs cement - 9 sxs gel - 600# hulls
Perforate at 900' - 1575' - 2260'.
Plug thru casing.

Plugging Proposal Received By: ROGER MOSES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/20/2000 10:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 215'. 5 1/2" casing at 3690'. 4 1/2" liner at 3692'.
Tied to 4 1/2" - pumped 40 sxs cement with 300# hulls followed with 9 sxs gel, followed by 120 sxs cement with 200# hulls to Max.
P.S.I. 1000#. S.I.P. 300#. *Annulus full of cement*
Total of 160 sxs 60/40 pozmix with 10% gel and 500# hulls and 9 sxs gel.

Remarks: ALLIED CEMENTING COMPANY. STEWART TANK - WATER.

Plugged through: CSG

District: 04

Signed Roger A. Moses
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
10-3-00
OCT 3 2000

SEP 22 2000

110
INVOICED
DATE 10/4/00
INV. NO. 2001060795

CONSERVATION DIVISION
Wichita, Kansas 67203

