

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21033-00-00
Spot: CNESESW Sec/Twnshp/Rge: 4-10S-19W
990 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: ONDRASEK Well Number: 1
County: ROOKS Total Vertical Depth: 3726 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

Conductor Pipe: Size feet: 121.10
Surface Casing: Size 8.625 feet: 196 140 SX CMT
Production: Size 4.5 feet: 3726 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/08/2002 12:00 PM
Plug Co. License No.: 30717 Plug Co. Name: DOWNING-NELSON OIL CO INC
Proposal Rcvd. from: RON NELSON Company: DOWNING-NELSON OIL CO INC Phone: (785) 628-3449

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 250 sxs cement and 500# hulls.
Perforated at 925' - 1615' - 2017' with 2 shots each.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/08/2002 1:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 196' w/140 sxs cement. 4 1/2" casing at 3726' w/100 sxs cement.
Tied to 8 5/8" - pressured to 500# - took no cement.
Tied to 4 1/2" casing and squeezed 210 sxs cement with 500# hulls.
Max. P.S.I. 900#. S.I.P. 500#.
Total of 210 sxs 60/40 pozmix - 10% gel and 500# hulls.

RECEIVED
11-19-02
NOV 19 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger Moses
(TECHNICIAN)

NOV 15 2002

INVOICED Form CP-2/3
DATE 11-20-02
INV. NO. 2003060837

BLACK GOLD OIL COMPANY

P.O. BOX 26

#1 ONDRASEK

4-10-19W

HAYS, KS 67601

NE SE SW

CONTR PIONEER DRILLING

CTY ROOKS

GEOL

FIELD LYND

2196 KB CM 5/22/80 ^{CARD} ISSUED 9/25/80 IP P 15 BOPD & WTR

2191 GL
API 15-163-21,033

ARB OH 3721-3726

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
ANH		1577	+ 619
HEEB		3373	-1177
TOR		3395	-1199
LANS		3413	-1217
ARB		3720	-1524
RTD		3725	-1530
NO LOG			

8-5/8" 195.67/140sx, 4 1/2" 3721/100sx

NO DST'S
MICT - CC. (ARB OH), SWB SO, NAT, PF
(LKC J) 3586-90, AC 3000, SWB LD &
REC SSO, POP, P 15 BOPD & WTR;

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS