

To: 6 041129  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-24  
API NUMBER 15-163-00423-0000  
SE SW SE, SEC. 5, T 10 S, R 19 W/E  
330 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5245

Lease Name Sutor Well # 1

Operator: Okmar Oil Co.

County Rooks 122.36

Name & Address Box 723

Well Total Depth 3765 feet

Hays, Ks. 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 200' w/125 sks

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Hays, Ks.

Company to plug at: Hour: 1:30 PM Day: 24 Month: Jan Year: 19 90

Plugging proposal received from George Jorgenson

(company name) Okmar (phone)

were: 5 1/2" casing set at 3762' w/125 sks. Top perf at 3430'.

Perf anhy at 1675' and base dakota at 925'.

Ordered 450 sks 65/35 poz 10% gel w/1/4# f.c. plus 6 sks hulls.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5:30PM Day: 24 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 400 sks cement w/1/4# f.c. plus 5 sks hulls mixed in cement. Max 800#. S.I. 500#. psi.

Pumped in 8 5/8" casing 50 sks cement w/1/4# f.c. plus 1 sk. hulls mixed in cement.

Max 300#. S.I. 800# psi.

RECEIVED  
STATE CORPORATION COMMISSION  
2-14-90  
FEB 14 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED  
(If you do not observe this plugging.

DATE 2-16-90

INV. NO. 27472

Signed Dennis L. Hamel  
(TECHNICIAN)

Dennis L. Hamel