

6 041147

11-5

71P

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,064-0000

NW, SEC. 5, T 10 S, R 19

4290 feet from S section line

3230 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6931

Lease Name Hamel Well # 5

Operator: Bowman Oil Co.

County Rooks 64.09

Name & Address Box 17

Well Total Depth 1972 feet

Codell, Kansas 67630

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 213 cwc

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number

Address Russell, Ks.

Company to plug at: Hour: 8:00 AM Day: 4 Month: Nov Year: 19 89

Plugging proposal received from Don Bowman

(company name) Bowman Oil (phone)

were: Co. lost circ at 7:00 P.M. Nov 3, 1989: drill pipe and bit dropped at 2' at 1900'.

Operator mixed and spotted at 1972' - 160 bbls of heavy mud: no circ: Spot 100 sks

common w/1/4# f.c. plus 3% cc at 1972': p.d.p. wait 4 hrs.:

R.I.H. w/d.p. to tag cement. No cement: Co decides to plug the hole.

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 12:00 P.M. Day: 5 Month: Nov Year: 19 89

ACTUAL PLUGGING REPORT R.I.H. w/d.p. to t.d. Spot 200 sks common w/5% salt and

3% cc w/1/4# f.c. followed w/40 bbls heavy mud. P.O.O.H. w/d.p.: Wait 4 hours: R.I.H. w/d.p. to check fill up. No fill up. Pumped 40 bbls heavy mud followed w/200 sks 60/40 poz

6% gel w/4% cc plus 1/4# f.c. and 8 sks hulls: P.O.O.H. w/d.p.: Wait 8 hrs on cement: R.I.H. w/d.p.: Tagged top of cement at 950': Mixed 155 sks 60/40 poz 6% gel w/1/4# f.c. to circ

cement: P.O.O.H. w/d.p.: Filled hole to surf. w/cement: Plugged rathole w/15 sks cement.

Remarks: RECEIVED

If additional description is necessary, use BACK of this form.)

INVOICED 1000  
DATE 3-26-90  
Wichita, Kansas

Signed Dennis T. Hamel (TECHNICIAN)  
Dennis Hamel