

To: 6 041082
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-25 15-163-01892-0000
API NUMBER 15- 7-27-62

TECHNICIAN'S PLUGGING REPORT

Operator License # 6931
Operator: Bowman Oil Co.
Name & Address: Box 37
Codell, Ks. 67630

NW, SEC. 5, T 10 S, R 19 W/E
4290 feet from S section line
3630 feet from E section line
Lease Name Hamel Well # 2
County Rooks 122.14
Well Total Depth 3758 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 170' w/125 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____
Address Hays, Ks.

Company to plug at: Hour: 9:00AM Day: 25 Month: Oct Year: 19 89

Plugging proposal received from Don Bowman
(company name) Bowman Oil (phone) _____

were: 5 1/2" casing set at 3756.5 w/150 sks; D.V. at 1668.5' circ w/500 sks cement.
Open hole 3756 - 58: R.B.P. at 3000' w/2 sks sand on plug; Casing bad at
2100' - 2300': lost circ during cleanout: Pumped in at 20 sks hulls w/150 sks
gel followed w/500 sks cement. T.O.C. 1500' drilled to 1790'; lost circ:
Abd to plug: Ordered 300 sks 65/35 poz 10% gel w/1/4# f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00 Day: 25 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Hooked up to 5 1/2" pumped in 50 sks cement no hulls, followed w/
250 sks cement plus 9 sks hulls in cement. Max psi 300#. Shut in psi 100#
Hooked up to 8 5/8" s.p. Pressured up to 400# psi.

RECEIVED
STATE CORPORATION COMMISSION
11-14-89
NOV 14 1989

Remarks: _____
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel

DATE 11-15-89
INV. NO. 26459
10-25

JAN 19 1990