

4-041406

9-22

15-163-01895-0000

277
R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - N/A

SE SW SW /4 SEC. 06, 10 S, 19 W
330 feet from S section line
4290 feet from E section line

Operator license# 5337

Lease Gish well # 2

Operator: Nadel & Gussman

County Rooks

Address: 3200 First National Tower
Tulsa, Oklahoma 74103

Well total depth 3785 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 160 feet
w/125 sx.

123.01

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 1:00P.M. Day: 22 Month: September Year: 92

Plugging proposal received from: Frank Neff

Company: Nadel & Gussman Phone: 918-583-3333

Were: 5 1/2" casing set @ 3785' w/100 sx. cement. Perf. @ 3623'- 3627'.
Squeezed @ 1735' w/375 sx. 1096' w/250 sx. 730' w/325 sx.
Ordered 400 sxs. 60/40 pozmix - 8% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 3:15P.M., Day: 22, Month: September, Year: 92

Actual plugging report: Hooked-up to 5 1/2" casing. Pumped in 25 sx. cement followed with 250 sx. cement with 400# hulls mixed in cement. Max. P.S.I. 700#. S.I.P. 400#.

Hooked-up to 8 5/8" S.P. Pumped in 50 sx. cement w/100# hulls in cement. Max. P.S.I. 600#. S.I.P. 300#.

RECEIVED
STATE CORPORATION COMMISSION

10-5-92
OCT 5 1992

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING X. Elevation: GL

CONSERVATION DIVISION
Wichita, Kansas

I did [X] / did not [] observe the plugging.

Dennis J. Hamel

HD

(agent)

Form CP-2/3

INVOICED
DATE OCT 16 1992
INV. NO. 36476