

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-30227-00-01  
Spot: CSENWNW Sec/Twnshp/Rge: 9-10S-19W  
4290 feet from S Section Line, 4290 feet from E Section Line  
Lease/Unit Name: BALDWIN OWWO Well Number: 2  
County: ROOKS Total Vertical Depth: 3757 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 372  
HAYS, KS 67601

Production Casing Size: 5.5 feet: 3754 w/125 sxs cmt 122.10  
Surface Casing Size: 8.625 feet: 168 w/100 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2003 11:00 AM  
Plug Co. License No.: 30717 Plug Co. Name: DOWNING-NELSON OIL CO INC  
Proposal Rcvd. from: RON NELSON Company: DOWNING-NELSON OIL CO INC Phone: (785) 628-3449

Proposed Plugging Method: According to KCC Rules & Regulations.  
Ordered 335 sxs cement and 500# hulls.  
Perfs at 950' and 1650'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/26/2003 12:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 168' w/100 sxs cement. 5 1/2" casing at 3754' w/125 sxs cement.  
Tied to 5 1/2" casing and squeezed 300 sxs cement and 500# hulls.  
Max. P.S.I. 800#. S.I.P. 500#.  
Tied to 8 5/8" x 5 1/2" annulus - immediate pressure - took no cement.  
Cement evident at bull plug.  
Total of 300 sxs 60/40 pozmix - 10% gel and 500# hulls.  
Dakota 634' - 934'. Anhydrite 1606' - 1646'.

RECEIVED  
KANSAS CORPORATION COMMISSION  
4-2-03  
APR 02 2003  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: CSG

District: 04

Signed Roger D. Moses  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-3-03

INV. NO. 2003061372

MAR 28 2003

DRELLING & JENNINGS #2 BALDWIN 'OWWO' SE: NW: NW 9-10-19W

Contr. LEO DRELLING Cty. ROOKS

Geol. F. WHISLER Pool LYND SO CONE

E. 2220 KB Cm. Cp. 3/13/69 IP P 30 BOPD + 15% W

LANS 3476-80, 3493-96  
& 3592-95 (GR 34.2)


SMP Tops	Depth	Datum
ANH	1606	+614
HEEB	3403	-1183
TOR	3423	-1203
LANS	3441	-1221
BKC	3643	-1423
CONG	3676	-1456
ARB	3752	-1532
TD	3757	-1537
CORRECTED CARD:		
LANS POT ADDED		

Csg. 8"168/100sx; 5" 3754/125sx  
 OLD INFO: WAS SAME OPER. COMM  
 11/1/66; COMP 12/8/66; P 61 BOPD  
 N/W ARB 3754-57 GR 26  
 DST 3409-32/1', 15'M, BHP 893-  
 138#/30", FP 23-23#  
 DST 3466-3506/1', 600'WTR, SSO,  
 180'OILY WTR, 180'W, BHP  
 690-671#, FP 205-446#  
 DST 3519-50/1', 150'GIP, 240'M  
 GSY OIL, 360'OILY W, BHP  
 844-828#, FP 42-284#  
 DST 3574-57/1', 690'CO, BHP 706-  
 682#, FP 65-292#  
 CO TD 3757, FU 2250'O/NW 12 HRS  
 NEW INFO: PF 3476-80, /3493-96,  
 3522-24; 3592-95 AC CO & POP  
 NEW PAY

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS