

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-30206-00-01
Spot: CSWNWNW Sec/Twnshp/Rge: 9-10S-19W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: BALDWIN OWWO Well Number: 1
County: ROOKS Total Vertical Depth: 3768 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 173 100 SX CMT
Production: Size 5.5 feet: 3760 150 SX CMT
Liner: Size feet: 122.46

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/01/2001 10:30 AM

Plug Co. License No.: 30717 Plug Co. Name: DOWNING-NELSON OIL CO INC

Proposal Rcvd. from: RON NELSON Company: DOWNING-NELSON OIL CO INC Phone: (785) 628-3449

Proposed Plugging Method: According to KCC Rules and Regulations.
Ordered 350 sxs cement and 500# hulls.
Perforate at 940' - 1580' - 2090'.

Plugging Proposal Received By: ROGER MOSES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/01/2001 12:40 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 173' w/100 sxs cement. 5 1/2" casing at 3760' w/150 sxs cement.
Tied to 5 1/2" casing - pumped 295 sxs cement and 500# hulls to Max. P.S.I. 700#. S.I.P. 300#.
Tied to 8 5/8" S.P. - pumped 55 sxs cement to Max. P.S.I. 300#. S.I.P. 150#.
Total of 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Dakota at 550' - 890'.
Anhydrite at 1565' - 1600'.
Salt at 1900' - 2042'.

RECEIVED
AUG 13 2001
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

INVOICED
DATE 8-14-01
INV. NO. 2002060226

District: 04

Signed Roger Moses
(TECHNICIAN)

107

AUG 08 2001

DREILING & JENNINGS #1 BALDWIN 'QWWO' 9-10-19W
SW NW NW

Contr. LEO J. DREILING & SONS City. ROOKS

Geol. DICK ROBY Pool LYND SQ. POOL

E. 2220 KB Cm. Cp. 2/20/69 IPP 28 BOPD +10%w/
OPENER
TOR 3422-25 &
LANS 3474-3535

LOG Tops	Depth	Datum
HEEB	3400	-1180
TOR	3421	-1201
LANS	3440	-1220
BKC	3644	-1424
ARB	3755	-1535
LTD	3764	-1544
RTD	3768	-1548

Csg. GR 34.2
8" 173/100 SX 5" 3760
OLD INFO: WAS SAME OPERATOR COMM 8/31/66
COMP 10/13/66 ST TST: FMP 68 BOPD, NW/
ARB 3760-68) GR 20
DST 3411-36/1', 180' HOCH, BHP 1056-954#
FP 24-78#
DST 3524-49/1', 1000' GIP, 120' HOCH,
300' MDY O, 200' FREE O, 180' OCWM,
BHP 844-830#, FP 70-375#
DST 3591-3621/1', 15' DRLG M, FBHP 422#;
FP 12-12#
DST 3763-68/1', 1440' O, BHP 1056-998#
FP 186-552#
COTD. 3768; FU 2000' O/8 HRS, NO SWB TST;
POP

(OVER)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

*No PFA
on Squeezers*

DREILING & JENNINGS #1 BALDWIN 9-10-19W
SW NW NW

NEW INFO: PB 12/3422-25 (TOR) 12/3474-77, 12/3492-95, 8/3522-24, 12/3532-35
1000 ACID. SWB LD. POP. COMP. DUAL PRODUCER /ARB & TOR-LANS