

15-163-00228-0001  
5-18  
179  
R

4-041386

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 8-19-1949

SE SW SW /4 SEC. 07, 10 S, 19 W  
330 feet from S section line  
4290 feet from E section line

Operator license# 5310 Lease Dunlap well # 2

Operator: Four Way Operations, Inc. County Rooks

Address: P.O. Box 698 Well total depth 3815 feet  
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 251 feet

123.98

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:30A.M. Day: 18 Month: May Year: 92

Plugging proposal received from: Jim Rockhold

Company: Four Way Operations, Inc. Phone: \_\_\_\_\_

Were: 5 1/2" casing set @ 3793' w/NA cement. Open hole @ 3793'-3815'.  
Anhy.-Perf. @ 1650'. Dakota @ 950'. W.L.M. 3800'. T.O.F. @ 1465'.  
Ordered 350 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 4:30P.M., Day: 18, Month: May, Year: 92

Actual plugging report: Hooked-up to 5 1/2" casing. Squeezed 325 sx.  
cement w/500# hulls. Max. P.S.I. 800#. Shut in P.S.I. 400#. Hook-up  
to 8 5/8" S.P. Max. P.S.I. 500#. Hooked-up to 8 5/8" and pressured up  
to 500# max. cement at surface.

RECEIVED  
STATE CORPORATION COMMISSION  
7-14-92  
JUL 14 1992  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Casing appears to have been squeezed at various intervals.

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO

Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO

Plugged through TUBING \_\_\_\_\_, CASING  . Elevation: 2230 GL RECEIVED

I did[  ] / did not[  ] observe the plugging.

Dennis L. Hamel  
STATE CORPORATION COMMISSION  
(agent) JUL 14 1992

INVOICED  
DATE 8-4-92  
INV. NO. 35846