

7-22

15-163-02698-0001

4-041905

D-03,021

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1949

SW NW NE /4 SEC. 07, 10 S, 19 W
990 feet from N section line
2310 feet from E section line

Operator license# 5337

Lease: Ouderkirk Well # 5

Operator: Nadel & Gussman

County: Rooks 141.08

Address: 3200 First National Tower
Tulsa, OK 74103

Well total depth 4341 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 188 Feet
W/145 sxs cmt.

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 22 Month: July Year: 1997

Plugging proposal received from: Art Rolo

Company: Berexco, Inc. Phone:

Were: 5 1/2" casing set at 4183' w/708 sxs cement. O.H. at 4183' - 4341'.
3 1/2" tubing to 560', followed with 2 7/8" tubing to 4000' sanded in.

Ordered 200 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 200# hulls.

7-29-97
D 11 16
1997 JUL 29 10 16 AM
D 11 16

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:00 P.M., Day: 22, Month: July, Year: 1997

Actual plugging report: Ran in hole with 1" tubing to 3300', hit sand fill. Pulled out of hole with tubing. Bad casing at 2300'. Perf casing at 2150' - 1690'. Run in hole with 1" tubing - hit bad spot at 2300'. Pulled one joint tubing. Spotted 40 sxs cement with 1/4# flocele to circulate cement at surface. P.O.O.H. with tubing. R.I.H. with perforators and shot casing and tubing at 950'. Released perforations. Rig-up cementers to 3" tubing and squeezed with 125 sxs cement with 1/4# flocele. Max. P.S.I. 750#. S.I.P. 600#. Rig up cementers to 8 5/8". Squeezed 35 sxs cement with 100# hulls. Max. P.S.I. 400#. S.I.P. 200#.

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: G.L.

I did [X] / did not [] observe the plugging.

Dennis Hamel
(agent)

Form CP-2/3

INVOICED

DATE JUL 30 1997

INV. NO. 48693

B