

4 050095

3-5 15-163-30112-0001 287 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- D-12,219  
C NE SW, SEC. 7, T 10 S, R 19 W/E<sup>XX</sup>

1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Atherton Well # 2 SWD

Operator: Ritchie Exploration Inc  
Name & Address: 125 N. Market  
Wichita, Ks. 67202  
316-267-4375

County Rooks  
Well Total Depth 3824 PBT 1600 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 178

Abandoned Oil Well Gas Well Input Well SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. License Number 4-3-91  
Address  
RECEIVED STATE CORPORATION COMMISSION APR 03 1991

Company to plug at: Hour: AM Day: 5 Month: Mar Year: 1991

Plugging proposal received from John Niernberger

(company name) (phone)

were: Ordered 280 sks cement (230 sks 65/35 poz 6% gel 50 sks common)

Well record: 8 5/8 set at 178 w/100 sks. 4 1/2 set at 1600 w/550 sks.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 12:30PM Day: 5 Month: Mar Year: 1991

ACTUAL PLUGGING REPORT Ran tubing to 1330. Pumped 50 sks common

cement down tubing then 130 sks 65/35 poz 6% gel cement circ. Pulled tubing tied onto 4 1/2 casing sq w/100 sks 65/35 poz 6% gel and 100 bs. hulls 100 max psi and 50. Shut in psi. Backside cement visible at surf.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 4-9-91  
SER. NO. 31428

J.S.

Signed Marvin Miller (TECHNICIAN)