

10-2
15-163-01908-0000 28

6-010768

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- 7-3-1949
NW SE NW /4 SEC. 7 , 10 S, 19 W
_____ feet from S section line
_____ feet from E section line

Operator license# 5337 Lease Oderkirk well # 3

Operator: Nadel & Gussman County Rooks

Address: 3200 1st National Tower
Tulsa, OK 74103
Well total depth 3774 feet 122.65
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 196 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Nadel & Gussman License# 5337

Address: 3200 1st National Tower - Tulsa, OK 74103

Company to plug at: Hour: A.M. Day: 2 Month: October Year: 91

Plugging proposal received from: Frank Neff

Company: Nadel & Gussman Phone: _____

Were: Order 350 sx. 60/40 pozmix - 8% gel. - 500# hulls. Run tubing to 3490'. Anhydrite 1640'. Well was squeezed @ 1560' w/250 sx. and 780' w/150 sx. Dakota 642'- 942'. Plug @ 3500'.

Plugging Proposal Received by: Dale F. Balthazor
Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:15A.M. Day: 2 Month: October Year: 91

Actual plugging report: Pumped down tubing 150 sx. Laid down 2000' tubing. Pumped down 100 sx. circulated. Laid down tubing and pumped down 8 5/8" 75 sx. w/200# hulls. Max. pressure 200# w/100# Closed w/100#. Pumped down 5 1/2" casing. 40 sx. Max. pressure 200# Closed 200#.

10-10-91
OCT 10 1991

Remarks: By: Allied Cement. CONSERVATION DIVISION
WICHITA, KS

INVOICED

I did / did not observe the plugging.

DATE 10-30-91
INV. NO. 33563

Rick S.

Dale F. Balthazor

(agent)
Form CP-2/3