

10-2
6-010769 15-163-01912-0000p 29

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- 3-2-1951
NE NW NW /4 SEC. 7, 10 S, 19 W
_____ feet from S section line
_____ feet from E section line

Operator license# 5337 Lease Oderkirk well # 9

Operator: Nadel & Gussman County Rooks

Address: 3200 1st National Tower Well total depth 3773 feet *122.62*
Tulsa, OK 74103 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 164 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Nadel & Gussman License# 5337

Address: 3200 1st National Tower - Tulsa, OK 74103

Company to plug at: Hour: A.M. Day: 2 Month: October Year: 91

Plugging proposal received from: Frank Neff

Company: Nadel & Gussman Phone: _____

Were: Order 350 sx. 60/40 pozmix - 8% gel. - 500# hulls. Run tubing to 3490'. Plug @ 3500'. Anhydrite 1640' - 1690'. Dakota 642' - 942'. Squeezed.

Plugging Proposal Received by: Dale F. Balthazor

Plugging operations attended by agent? All], Part], None]

Completed: Hour: 2:30P.M. Day: 2 , Month: October , Year: 91

Actual plugging report: Pumped down tubing 150 sx. cement 60/40 poz. - 8% gel. Pulled 2000' of tubing. Pumped down 100 sx. cement. Laid down tubing. Pumped down 8 5/8" 75 sx. cement w/200# hulls. Max. pressure 500#. Closed w/200#. Pumped down 5 1/2" casing 40 sx. cement. Max. pressure 400#. Closed w/200#.

RECEIVED
KANSAS CORPORATION COMMISSION
10-10-91

OCT 10 1991

Remarks: By: Allied Cement Company

CONSERVATION DIVISION
WICHITA, KS

Dale F. Balthazor

(agent)

Form CP-2/3

INVOICED

DATE 10-30-91

INV. NO. 33564

J. S.

I () do not observe the plugging.