

4-041617

9-21 15-163-01909-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - NA

SE NE NW /4 SEC. 07, 10 S, 19 W  
4290 feet from S section line  
2970 feet from E section line

Operator license# 5337 Lease Ouderkirk well # 4

Operator: Nadel-Gussman County Rooks

Address: 3232 First National Tower  
Tulsa, OK 74103  
Well total depth 3769 feet <sup>122.49</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 187 feet  
w/45 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 21 Month: September Year: 94

Plugging proposal received from: Art Rolo

Company: Nadel-Gussman Phone:

Were: 5 1/2" casing set @ 3768' w/125 sxs. cmt. Salt @ 2275' -  
Anhy. @ 1690' - Dakota @ 950' - Tubing fish @ 3320'.  
Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 400# hulls  
with 8 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 12:30P.M. Day: 21, Month: September, Year: 94

Actual plugging report: R.I.H. with tubing to 3300'. Spotted 35 sxs.  
cement with 200# hulls with 8 sxs. gel to 2300'. At 2300' spotted 100  
sxs. cement with 100# hulls. Pulled to 950' - spotted 40 sxs. cement  
to circulate at surface. Pulled tubing and squeezed casing with 75 sxs.  
cement. Max. P.S.I. 400#. 8 5/8" S.P. Squeezed 50 sxs. cement with  
100# hulls. Max. P.S.I. 300#.

Remarks:  
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO  
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING X, CASING. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

*Dennis L. Hamel*  
H.D.  
(agent)

RECEIVED  
STATE CORPORATION COMMISSION  
9:30-94  
SEP 30 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS

INVOICED

OCT 10 1994

DATE  
INV. NO. 41374