

4-041369

15-163-03372-0001309
5-18
R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 6-16-1950

SW SW SW /4 SEC. 07, 10 S, 19 W
330 feet from S section line
4950 feet from E section line

Operator license# 5310 Lease Dunlap well # 3

Operator: Four-Way Operations, Inc. County Rooks

Address: P.O. Box 698 Well total depth 3799 feet 123.46
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 255 feet w/circ. cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00A.M. Day: 18 Month: May Year: 92

Plugging proposal received from: Jim Rockhold

Company: Four-Way Operations, Inc. Phone:

Were: 5 1/2" casing set @ 3766' w/NA cement. Perf. @ 3766' - 3799'.
Anhy. perf. @ 1650'. Dakota @ 950'. W.L.M. 3780'. Squeezed @ 1155'
w/200 sx. plus 200 sx. (400 total). Possible squeeze @ 1300' & 880'.
Ordered 350 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 8:00P.M., Day: 18, Month: May, Year: 92

Actual plugging report: Run in hole with tubing to 1646'. Spot 125 sxs.
cir. cement. P.O.O.H. with tubing. Hooked-up to 5 1/2" casing.
Squeezed 150 sx. cement w/500# hulls.
Max. P.S.I. 700#. Shut in P.S.I. 300#. Hood-up to 8 5/8" S.P.
Squeezed 75 sx. cement. Max. P.S.I. 900#. Shut in P.S.I. 300#.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X NO
Plugged through TUBING X, CASING. Elevation:

I did [X], did not [] observe the plugging.

DATE 6-30-92

INV. NO. 35588

5-18

RECEIVED
STATE CORPORATION COMMISSION
Dennis L. Hamel
1992
6-1-92
(agent)
CONSERVATION DIVISION
Form 95-275
Wichita, Kansas