

15-163-01907-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SW SW NE NW, Sec. 7, T 10 S, R 19 W E
2310 ~~790~~ feet from N/S section line
2970 ~~7650~~ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5337
Operator: Nadel + Gussman
Name & Address 32nd, Fl. 1st. Natl. Tur.
Tulsa, Ok. 74103.

Lease Name Onderhirk Well # 2
County Roosha
Well Total Depth 3782 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8" feet 191

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co., Inc. License Number

Address Box 32, Russell, Ks. 67665

Company to plug at: Hour: 8:00 AM Day: 3 Month: 11 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Frank Neff

(company name) Nadel & Gussman (phone) 318-583-3333

were: Order 275 sacks 50 percent - 6% Gel. - 3% Gel. (L.), 4 sacks hulls

Signed Arthur E. Phelps
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:00 AM Day: 3 Month: 11 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 191' S.P. cas. w/ 185 sacks common. 5 1/2" set at 3777'
w/ 125 sacks common. Plugged bottom at 3500' w/ cast iron plug. squeezed at
1128' w/ 250 sacks + 1030' w/ 200 sacks. Perf. at 1650' + 630' w/ 2 shots.
Pumped in 8 5/8" + 5 1/2" - 275 sacks 50 percent - 6% Gel. - 3% Gel. (L.), w/ 4 sacks hulls
in cement.

Maximum pressure 200 pounds

Remarks:

RECEIVED
STATE CORPORATION COMMISSION
11-8-82

NOV 08 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 11-23-82
INV. NO. 1696-W

Signed Arthur E. Phelps
(TECHNICIAN)