

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

990 <sup>ENVL</sup> - 330 <sup>SENEFE</sup> NE, Sec. 9, T 10 S, R 19 W/E  
API NUMBER 15-162-21, 826-0000  
990 feet from N/E section line  
330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5562

Lease Name COLLINS Well # #2

Operator: LIBERTY ENTERPRISES  
Name &  
Address 308 WEST MILL  
PLAINVILLE, MO MS  
67663

County ROCK  
Well Total Depth 3825 feet  
Conductor Pipe: Size - feet -  
Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well - Gas Well - Input Well - SWD Well - D&A X

Other well as hereinafter indicated -

Plugging Contractor PIONEER DRILLING License Number 256

Address 308 WEST MILL PLAINVILLE, MS. 67663

Company to plug at: Hour: 5:00 PM Day: 17<sup>th</sup> Month: OCT Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO TOM ALM

(company name) PIONEER DRILLING INC (phone) 913-434-4687

were: 8 5/8" - 269 FE SP. CUL. BY ALLIED CEMENTING.

ORDERED 180 ST 50/50 FORMIX 6% GEL-3% CA-CL. & 8 5/8" PLUG.

SPOTTED WITH DRILL STEM WITH HEAVY MUD BETWEEN ALL PLUGS

1<sup>ST</sup> PLUG @ 3730 FE +/- 20 ST CNT. - 2<sup>ND</sup> PLUG @ 1590 FE +/- 20 ST CNT.

3<sup>RD</sup> PLUG @ 960 FE +/- 80 ST CNT. - 4<sup>TH</sup> PLUG @ 270 FE +/- 40 ST CNT.

5<sup>TH</sup> PLUG SOLID BRIDGE HULLS PLUG @ 40 FE +/- 10 ST CNT.

Signed Marian Schmidt  
(TECHNICIAN)

10<sup>ST</sup> RAT HOLE - (CIRCULATED)

Plugging Operations attended by Agent?: All - Part - None X

Operations Completed: Hour: 8:30 PM Day: 17<sup>th</sup> Month: OCT Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 269 FE SP. CUL. +/- 60/40 Pore-2% GEL-3% Ca-Cl.

ORDERED 180 ST 50/50 FORMIX 6% GEL-3% CA-CL. AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM WITH HEAVY MUD BETWEEN ALL PLUGS

1<sup>ST</sup> PLUG @ 3730 +/- 20 ST CNT. 2<sup>ND</sup> PLUG @ 1590 FE +/- 20 ST CNT.

3<sup>RD</sup> PLUG @ 960 FE +/- 80 ST CNT. - 4<sup>TH</sup> PLUG @ 270 FE +/- 40 ST CNT.

5<sup>TH</sup> PLUG SOLID BRIDGE HULLS PLUG @ 40 FE +/- 10 ST CNT. - 10<sup>ST</sup> RAT HOLE (CIRCULATED)

Remarks: CEMENTED BY ALLIED CNT.

RECEIVED  
STATE CORPORATION COMMISSION

10-26-82  
OCT 26 1982

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did did not) observe this plugging.

INVOICED

DATE 11-16-82

INV. NO. 1585-W

Signed Marian Schmidt  
(TECHNICIAN)