



Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION 1031369
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4058
Name: American Warrior, Inc.
Address 1: PO Box 399
Address 2: _____
City: GARDEN CITY State: KS Zip: 67846 + _____
Contact Person: Scott Corsair
Phone: (785) 398-2270
Type of Well: (Check one) ☐ Oil Well ☐ Gas Well ☐ OG ☒ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☐ SWD Permit #: _____
☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-135-24858-00-00
Spot Description: _____
NW NE SE SE Sec. 11 Twp. 19 S. R. 22 ☐ East ☒ West
1,317 Feet from ☐ North / ☒ South Line of Section
614 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☒ SE ☐ SW
County: Ness
Lease Name: Schwien Unit Well #: 1
Date Well Completed: 10/28/2008
The plugging proposal was approved on: 12/03/2008 (Date)
by: Mike Maier (KCC District Agent's Name)
Plugging Commenced: 12/03/2008
Plugging Completed: 12/04/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8.625	227	0
		Production	5.5	4337	3000

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Swift Services mixed 50 sacks of standard cement with 300# of hulls and pumped to perfs @ 4243-4326' overall and let sit overnight. The next day Perf Tech shot off casing @ 3000', H-D Oil Field Services pulled casing to 1500', Swift Services pumped 50 sacks of 60/40 poz, 4% gel and set balanced plug @ 1500', H-D pulled casing to 727' and Swift Services pumped 60 sacks of 60/40 poz, 4% gel and set balanced plug @ 650', H-D pull casing to 279' and Swift Services pumped 50 sacks of 60/40 poz, 4% gel and set balanced plug @ 240', H-D pull rest of casing and Swift Services top off 8 5/8" casing with 10 sacks of 60/40 poz, 4% gel. Well plugged.

Plugging Contractor License #: 32382 Name: Swift Services, Inc.
Address 1: PO BOX 466 Address 2: N HWY 283
City: NESS CITY State: KS Zip: 67560 + 0466
Phone: (785) 798-2300
Name of Party Responsible for Plugging Fees: American Warrior, Inc.
State of Kansas County, Ness, ss.
Scott Corsair ☒ Employee of Operator or ☐ Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
SEP 13 2009
KCC WICHITA