

15-163-01947-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME Marcotte

WELL NUMBER #7

SPOT LOCATION NE SW NW

SEC. 18 TWP. 10 SRGE. 19 or W

COUNTY Rooks

Date Well Completed 7/23/50

Plugging Commenced 4/16/85

Plugging Completed 4/16/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS 970 Fourth Financial Center, Wichita, KS 67202

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5245

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6 (Hays)

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Arbuckle Depth to top 3764' bottom 3766' T.D. 3766'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Anhydrite	Anhydrite	1640	73	8 5/8"	165'	0
Heebner	Shale	3426	30	5 1/2"	3765'	0
Toronto	Lime	3446	58			
Lansing	Lime	3464	3673			
Arbuckle	Dolomite	3764	66			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 200 sx 60/40 pozmix cement w/ 8% gel, 3% C.C., and 1/4#/sx Flocel w/hulls down casing. PT 100 sx cement down casing annulus.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sun Cementing  
Address Box 169 Great Bend, KS 67530

RECEIVED  
STATE CORPORATION COMMISSION  
5-13-85  
MAY 13 1985  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.


David W. Munro (employee of operator)  
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Munro

(Address) 970 Fourth Financial Center  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 10 day of May, 1985

Cecelia A. Bowser  
Notary Public



My Commission expires: August 5, 1987