

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

# 4 15-163-01955-0002  
 Docket No. 87,025-C

API NUMBER \_\_\_\_\_

LEASE NAME Scoggins

WELL NUMBER 6

1650 Ft. from S Section Line

3430  
2970 Ft. from E Section Line

SEC. 18 TWP. 10 RGE. 19 (X) or (W)

COUNTY Rooks

Date Well Completed 7/8/49

Plugging Commenced 10/18/89

Plugging Completed 10/18/89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Bowman Oil Company

ADDRESS P. O. Box 37 Codell, Ks 67630

PHONE# (913) 434-2304 OPERATORS LICENSE NO. 6931

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/17/89 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
			<u>1637</u>		<u>1637</u>	
		<u>0</u>	<u>1644</u>	<u>8 5/8</u>	<u>1644</u>	<u>none</u>
		<u>0</u>	<u>3817</u>	<u>5 1/2</u>	<u>3817</u>	<u>1200</u>
		<u>3780</u>	<u>3810</u>	<u>4 1/2</u>	<u>60</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Packer and 2 joints at 3800'. Ran tubing to 2520' and spotted 150 sx of cement with 600# hulls, pulled 40 joints and spotted 150 sx cement with 200# hulls, pulled 30 joints and spotted 50 sacks, cement, cement circulated, pulled rest of tubing and fillup, maximum pressure 300# shut in 150#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Service License No. \_\_\_\_\_

Address 1100 East 8th Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bowman Oil Company

STATE OF Kansas COUNTY OF Rooks

Louis D. Bowman (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have known the facts of the statements, and matters herein contained and the log of the above described well as filed the same are true and correct, so help me God.

(Signature) Louis D. Bowman

(Address) Box 37 Codell, Ks 67630

SUBSCRIBED AND SWORN TO before me this 19th day of October, 1989

Vesta J. Russell  
 Notary Public

My Commission Expires: July 17 1992

NOTARY PUBLIC - State of Kansas  
 VESTA J. RUSSELL  
 My Appt. Exp. 7-17-92

RECEIVED  
 STATE CORPORATION COMMISSION  
 10-23-89  
 OCT 23 1989

CP-4  
 Revised 5-88