

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-163-21692-0088
 LEASE NAME M. THOMAS
 RECEIVED
 9-6-02
 016 2006
 KCC WICHITA

WELL NUMBER 1-18
 NOTICE: Fill out completely 330 Ft. from S Section Line
 and return to Cons. Div. 1400 Ft. from E Section Line
 office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 18 TWP. 10S RGE. 19W (E) or (W)
 ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY ROOKS
 PHONE # () 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 6/18/82
 Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 8/30/02
 Plugging Completed 8/30/02

The plugging proposal was approved on 8/30/02 (date)
 by DENNIS HAMEL w/KCC Hays, KS. (KCC District Agent's Name).
 Is ACO-1 filed? YES If not, is well log attached? NO
 Producing Formation ARBUCKLE Depth to Top 3522 Bottom 3784 TD 3890'
 Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	372	8 5/8	372	0
		production	3890 4267	5 1/2	3890 4267	0
				PT. KCC		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Plugged well as follows: Tied onto 5 1/2" csg. Pumped 40 sxs 60/40 poz 10% gel & 700# hulls, 20 sxs gel, 110sxs 60-40 poz Max press 1000#, ISIP 900#. Tied onto 8 5/8" csg. Pumped 15 sxs 60-40 poz 10% gel. Max press. 500#, ISIP 500#. Well P/A. Witnessed and approved by Dennis Hamel w/ KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 3rd day of Sept., 2002

Notary Public - Barbara J. Dodson [Signature]
 My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



CR

ALLIED CEMENTING CO., INC.
P.O. BOX 31
RUSSELL, KS 67665
PH (785) 483-3887
FAX (785) 483-5566
FEDERAL TAX ID# 48-0727860

15-163-21692-0000

* INVOICE *

COPY

Invoice Number: 087985

Invoice Date: 08/31/02

RECEIVED

SEP 06 2002

RECEIVED

KCC WICHITA

SEP 05 2002

Sold Murfin Drilling Co.
To: 250 N. Water, St. #300
Wichita, KS
67202

RA 36/RK

Cust I.D.....: Murfin
P.O. Number...: M. Thomas #1
P.O. Date.....: 08/31/02

Due Date.: 09/30/02
Terms.....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	99.00	SKS	6.6500	658.35	T
Pozmix	66.00	SKS	3.5500	234.30	T
Gel	32.00	SKS	10.0000	320.00	T
Hulls	7.00	SKS	18.0000	126.00	T
Handling	200.00	SKS	1.1000	220.00	T
Mileage (38)	38.00	MILE	8.0000	304.00	T
200 sks @\$.04 per sk per mi					
Plug	1.00	JOB	475.0000	475.00	T
Mileage pmp trk	38.00	MILE	3.0000	114.00	T

All Prices Are Net, Payable 30 Days Following
Date of Invoice. 1 1/2% Charged Thereafter.
If Account CURRENT take Discount of \$245.17
ONLY if paid within 30 days from Invoice Date

Subtotal: 2451.65
Tax.....: 166.71
Payments: 0.00
Total....: 2618.36

15-163-21692-0000

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

R

DATE <u>8 30 02</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>10:00 AM</u>	JOB START <u>10:30 AM</u>	JOB FINISH
LEASE <u>METHUEN</u>	WELL # <u>1</u>	LOCATION <u>ZURICH ZW 45 12W</u>		COUNTY <u>ROCK</u>	STATE <u>KS</u>		
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR _____ OWNER _____

TYPE OF JOB 37A

HOLE SIZE _____	T.D. _____
CASING SIZE <u>5 1/2</u>	DEPTH _____
TUBING SIZE _____	DEPTH _____
DRILL PIPE _____	DEPTH _____
TOOL _____	DEPTH _____
PRES. MAX _____	MINIMUM _____
MEAS. LINE _____	SHOE JOINT _____
CEMENT LEFT IN CSG. _____	
PERFS. _____	
DISPLACEMENT _____	

CEMENT

AMOUNT ORDERED ZDD 60# 10% GEL

ZOGEL 700# HULLS

USED 165 SKS

COMMON	<u>99</u>	@	<u>665</u>	<u>658.95</u>
POZMIX	<u>66</u>	@	<u>355</u>	<u>234.30</u>
GEL	<u>32</u>	@	<u>16.00</u>	<u>320.00</u>
CHLORIDE		@		
<u>HULLS</u>	<u>7</u>	@	<u>18.00</u>	<u>126.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>200</u>	@	<u>1.10</u>	<u>220.00</u>
MILEAGE	<u>48</u>	@	<u>6.34</u>	<u>304.32</u>
RECEIVED				TOTAL <u>1862.57</u>

SEP 0 6 2002

EQUIPMENT

PUMP TRUCK	CEMENTER <u>MARK</u>
# <u>345</u>	HELPER <u>JAVE</u>
BULK TRUCK	
# <u>367</u>	DRIVER <u>CLEN</u>
BULK TRUCK	
# _____	DRIVER _____

REMARKS:

KCC WICHITA SERVICE

MOVED 15 SKS DOWN 878 PRES. TO 500'

MOVED 40 SKS W/700# HULLS DOWN 5 1/2'

ZOGEL - 110 SKS

MAX PRES - 1000'

SHUT IN - 900'

DEPTH OF JOB _____	
PUMP TRUCK CHARGE _____	<u>475.00</u>
EXTRA FOOTAGE _____	@ _____
MILEAGE <u>38</u>	@ <u>3.00</u> <u>114.00</u>
PLUG _____	@ _____
	@ _____
	@ _____
TOTAL <u>589.00</u>	

CHARGE TO: MURFIN

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____
_____	@ _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAY

SIGNATURE John Gust

PRINTED NAME _____