

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-163-30215-0000

API NUMBER Comp. 7-12-66

LEASE NAME Anderson

WELL NUMBER 9

4290 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 18 TWP. 10S RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 7-12-66

Plugging Commenced 9-24-87

Plugging Completed 9-24-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR ROBERT R. PRICE OPERATING, INC.

ADDRESS P.O. Box 470442, Tulsa, Ok. 74147

PHONE# (918) 492-1694 OPERATORS LICENSE NO. 6273

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks.

Is ACO-1 filed? NA If not, is well log attached? Yes

Producing Formation Arb-LKC Depth to Top 3464 Bottom 3806 T.D. 3806

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation LKC	Content Oil	From	To	Size	Put in	Pulled out
Arbuckle	Oil	0	215	8 5/8"	215'	0
		0	3805	5 1/2"	3805'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Shoot 4 holes at 1645', Pump 15 sx. cement down casing. Pump 235 sx. of cement with 500# of hulls. Maximum pump pressure and shut-in pressure of 400#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ROBERT R. PRICE OPERATING, INC License No. 6273

Address P.O. Box 470442, Tulsa, Ok. 74147

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Robert R. Price Operating, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
 Robert R. Price, President

(Address) P.O. Box 470442, Tulsa, Ok. 74147

SUBSCRIBED AND SWORN TO before me this 26th. day of October, 19 87

My Commission Expires: 12-26-88

STATE CORPORATION COMMISSION PUBLIC CLERK LADRA GORRELL

OCT 28 1987
 10-28-87

CONFIRMED BY SECTION
 WICHITA, KANSAS

Form CP-4
 Revised 08-84

DRILLER'S LOG

COMPANY: Norman Oil Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: ANDERSON #9
 LOCATION: SE NW NE Sec. 18-10S-19W
 ROCKS COUNTY, KANSAS
 COMMENCED: 7-1-66
 COMPLETED: 7-12-66

0	60	Clay, Post Rock
60	140	Sand, Shale
140	910	Shale
910	1360	Sand, Shale
1360	1637	Redbed
1637	1673	Anhydrite
1673	2330	Shale, Shells
2330	2565	Lime, Shale
2565	2950	Shale
2950	3095	Shale, Lime
3095	3280	Lime, Shale
3280	3790	Lime
3790	3806	Arbuckle
	<u>3806</u>	<u>RTD - Set 5 1/2" Casing</u>

Set 8 5/8" 8 rd. 24# used surface casing @ 215' cemented with 165 sacks Common with GL3

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Anderson #9 well, located SE NW NE of Section 18, Township 10 South, Range 19 West, Rooks County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 15th day of July, 1966.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1967

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 28 1967
 CONSERVATION DIVISION
 Wichita, Kansas