

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-01945-0000

API NUMBER 4-50

LEASE NAME Marcotte

WELL NUMBER 5

SPOT LOCATION SW NW NW

SEC. 18 TWP. 10 RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 4-50

Plugging Commenced 4-20-90

Plugging Completed 4-20-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 3781

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	184	8 5/8		None
	Casing	0	3777	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each sat. Rig up Mercury and perf. 2 shots at 1650' and 2 at 950'. TD. 3690'. TIH 2 3/8 tubing to 3676.26'. Spot 90 sks 65/35 pos, 10% gel, 1/4# celloflake per sk. 200# hulls Pull 30 jts. to 2725.83 spot 135 sks 65/35 pos, 10% gel, 1/4# celloflake per sk. 100# hulls. Cement to surface. 10H with tubing. Hook to annulus Pressure to 450#. Shoot 2 holes at 184'. Hook up to casing pump 125 sks 65/35 pos, 10% gel 1/4# celloflake per sks 100# hulls. Mix 1000# Shut in 350#.

Name of Plugging Contractor Okmar Oil Company License No. 5245
Address Box 723 Hays, Kansas 67601

Bj Titan Cementer

STATE OF Kansas COUNTY OF Ellis, ss.


Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Kansas 67601

SUBSCRIBED AND SWORN TO before me this 23 day of April, 1990

Rosemary Smith
Notary Public



4-24-90
1990
SUBSCRIPTION DIVISION
Wichita, Kansas

My Commission expires: