

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-20107-0001

LEASE NAME Anderson

WELL NUMBER 11

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4290 Ft. from S Section Line

000 Ft. from E Section Line

SEC. 18 TWP. 10S RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 12-20-82

Plugging Commenced 1-16-90

Plugging Completed 1-16-90

LEASE OPERATOR ROBERT R. PRICE OPERATING, INC.

ADDRESS P.O. Box 470442, Tulsa, Oklahoma 74147

PHONE# (918) 492-1694 OPERATORS LICENSE NO. 6273

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-16-90 (date)

by Donald Butcher (KCC District Agent's Name).

Is ACO-1 filed? yes, 12-82 If not, is well log attached? \_\_\_\_\_

Producing Formation Granite Wash Depth to Top 3996 Bottom 4075' T.D. 4075'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Granite Wash	Water	3996	4075	8 5/8"	247'	None
Arbuckle	Water	3781	3996	5 1/2"	4074'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Set packer at 2100'. Pumped 175 sx. plug from 2100-4022. Set packer at 650'. Pumped 400 sx plug from 650' to 2100'. Pumped 300 sx plug down backside. Pumped two additional 250 sx. plugs to 1010' and 1143' after drilling out cement. Ran wireline to 1143'. Perforated at 930'. Pumped 115 sx. at 350 psi. SI w/300 psi. Pumped backside w/600 psi 0 sx.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BJ Titan License No. \_\_\_\_\_

Address Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robert R. Price Operating, Inc.


STATE OF Oklahoma COUNTY OF Tulsa, ss.

Robert R. Price (Employee of Operator) or (~~XXXXXX~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

Robert R. Price President

(Address) P.O. Box 470442, Tulsa, Oklahoma 74147



SUBSCRIBED AND SWORN TO before me this 6th. day of February, 19 90

[Signature]  
Laura Correll

My Commission Expires: 12-26-92

My Commission Expires Dec. 26, 1992