

15-163-01938-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 6-10-49  
LEASE NAME Anderson  
WELL NUMBER 1  
SPOT LOCATION NE NE NE  
SEC. 18 TWP. 10S RGE. 10 (E) or (W)  
COUNTY Rooks  
Date Well Completed 6-10-49  
Plugging Commenced 9-24-87  
Plugging Completed 9-24-87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR ROBERT R. PRICE OPERATING, INC.  
ADDRESS P.O. Box 470442, Tulsa, Ok. 74147

PHONE # (918) 492-1694 OPERATORS LICENSE NO. 6273

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks.

Is ACO-1 filed? NA If not, is well log attached? Yes

Producing formation Arbuckle-LKC Depth to top 3454' bottom 3874' T.D. 3874'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	0	235	10-75" <sup>at well</sup>	235'	0
LKC	Oil	0	3873	7"	3873'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Shot 4 hole at 1620'. Pump 50 sx. of cement down casing. Pump 400 sx. of cement mixed with 700# of hulls down casing. Maximum pump pressure and shut-in pressure was 750#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Robert R. Price Operating, Inc. License No. 6273  
Address P.O. Box 470442, Tulsa, Ok. 74147

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Robert R. Price Operating, Inc. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as recited that the same are true and correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
10-28-87  
OCT 28 1987

(Signature) [Signature]  
Robert R. Price, President  
(Address) P.O. Box 470442, Tulsa, Ok. 74147

CONSERVATION DIVISION  
Wichita, Kansas  
SUBSCRIBED AND SWORN TO before me this 26th day of October, 1987

[Signature]  
Notary Public LAURA GORREL

My Commission expires: 12-26-88

RECORD OF WELL No. 1

Olive Anderson FARM

(Show all measurements from surface level)

FORMATION AND COLOR	THICK- NESS OF STRATA	TOTAL DEPTH	FORMATION	THICK- NESS OF STRATA	TOTAL DEPTH
Bottom Cellar - Surface Level		5'			
Surface Level - Rig Floor		3'			
Rig Floor - Top Rotary Bushing		1'			
Drillers Log Corrected to Surface Level Meas.					
Sand		70'			
Shale & Shells		246'			
Set 10-3/4" at 240' w/150 sx					
Shale & Shells		516			
Sand & Shale		716			
Shale & Red Bed		776			
Sand & Shale		916			
Sand		1046			
Shale & Shells		1081			
Sand & Shale		1371			
Shale & Shells		2116			
Shale		2281			
Lime & Shale		2756			
Shale & Lime		3196			
Lime		3386			
Lime & Shale		3451			
Lime		3661			
Lime & Shale		3706			
Conglomerate		3740			
Congl. & Lime		3781			
Lime		3870 TD-drld.			
Top Lansing 3450'					
Simpson Sand 3746'					
Simpson Dol. 3759-3765'					
Simpson Shale 3765-3769'					
Conglomerate 3713'					
Arbuckle 3769'					
Set 7"OD csg at 3869' w/150 sx cnt					
Top cement plug at 3834' not drilled..					
Completed Plugged back TD 3834' surface level meas.					