


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County, Sec. 18 Twp. 10 Rge. 19W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE SE NW
Lease Owner Oklahoma Fracturing Services, Inc.
Lease Name Anderson #8 Well No.
Office Address Oklahoma City, Oklahoma 73112
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10/11/72 19
Plugging completed 10/12/72 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total Depth of Well 3785 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	188	none
				7"	3781'	694'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, ran sand to 3600' and dumped 6 sacks of cement.
Loaded hole, shot pipe at 700', pulled 22 joints. Pumped well with 3 sacks hulls, 25 sacks gel and 130 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
10-19-72
OCT 19 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 17th day of October, 1972



MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

My commission expires

Margaret Melcher
Notary Public.

15-163-01966-0000

RECORD OF WELL No. 8 Olive Anderson FARM
(Show all measurements from surface level)

FORMATION AND COLOR	THICK- NESS OF STRATA	TOTAL DEPTH	FORMATION	THICK- NESS OF STRATA	TOTAL DEPTH
---------------------	--------------------------------	----------------	-----------	--------------------------------	----------------

Surface Level - Derrick Floor 2'
 Derrick Floor - Rotary Kelly Bushing 3'
 Zero; Top Rotary Bushing to Top Spider 7.85'

Drillers Log
 Surface Level Measurements

Shale-Sand	185'
Set 10-3/4" csg at 188' w/200 sx cmt	
Shale-Shells	585
Shells-Shale,	1040
Anhydrite	1686
Shale-Shells	2195
Shale-Lime	2390
Shale-Shells	2500
Lime-Shale Streaks	2515
Lime	2575
Lime-Shale Streaks	2580
Lime-Shale	2725
Shale-Lime Streaks	2820
Shale-Lime	2860
Shale-Lime Steaks	2970
Shale-Lime	3040
Lime-Shale	3226
Lime-Shale-broken	3347
Lime	3365
Lime-Shale Streaks	3412
Lime	3685
Lime-Shale	3740
Lime	3757
Lime-Shale-Congl.	3783 TD
Set 7"OD csg at 3776' w/ 250 sx cmt	
Sample Tops; Topeka	3219'
Heebner Shale	3425-28'
Toronto	3448-60.
Lansing	3466
Conglomerate	3703
Simpson	3756
Arbuckle	3776

990' fr S. Line
 330' fr W. Line of
 E 50 A. NW 1/4
 18-10S-19W.
 Rooks County

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 17 1972
 CONSERVATION DIVISION
 Wichita, Kansas