


15-163-00721-000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County, Sec. 18 Twp. 10 Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines NE/NE/SE

Lease Owner MORGANSTERN & SPECTOR SE

Lease Name Foulke Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 10-4-54 19

Application for plugging filed February 19, 1956 19

Application for plugging approved February 20, 1956 19

Plugging commenced February 24, 1956 2-25- 19 56

Plugging completed 2-29- 19 56

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production January 31, 19 56

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 3782 Bottom 3784 Total Depth of Well 3784 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle				5 1/2"	3784'	2519'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging started 2-25-56 and completed 2-29-56. Cleaned out cellar and measured in to TD 3784'. Plugged off bottom with sand back to 3760' and dumped in 4 sacks of cement with bailer. Shot casing off at 2520' and pulled pipe out of hole. Plugged well as follows: Filled hole with heavy mud to 180'; set permanent rock bridge; and dumped in 15 sacks of cement. Filled hole with heavy mud to 35' of top; set permanent rock bridge; and dumped in 10 sacks of cement for cap on well.

Name of Plugging Contractor J. O. FORBES d/b/a FORBES CASING PULLING CO.
Address P. O. Box 221, GREAT BEND, KANSAS

STATE OF Kansas, COUNTY OF Russell, ss.
Morganstern & Spector (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. O. Morganstern*
Box 661 - Russell
(Address)

SUBSCRIBED AND SWORN to before me this 9 day of March, 1956

My commission expires April 14-1959

W. Schmidt
Notary Public.
3-8-56

PLUGGING
FILE SEC 18 T 10 R 19W
BOOK PAGE 39 LINE 29


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- UNITED DRILLING, INC.
Farm- Foulke No. 1

SEC. 18 T. 10 R. 19W
NE SE SE

Total Depth. 3784
Comm. 9-20-54 Comp. 10-4-54
Shot or Treated.
Contractor.
Issued. 2-19-55

County Rooks KANSAS



Elevation. 2209

Production. 25 bbls. per day

CASING:

8 5/8" 183'

Figures indicate Bottom of Formations.

sand & shale	100
shale	183
sand & shells	990
sand & shale	1080
redbed	1390
redbed & shale	1565
Anhydrite	1625
shale & shells	1650
shale & lime	2365
shale & shells	2850
shale & lime	2915
shale & lime shells	3020
shale & shells	3120
shale & lime	3216
lime	3444
Conglomerate	3660
Conglomerate & shale	3715
lime	3767
Arbuckle	3784
Total depth	

Scout Tops:

Lansing	3458
Base Kansas City	3658

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
PAGE SEC 18 T 10 R 19W
BOOK PAGE 39 LINE 29