

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-23,115-0000

LEASE NAME Scoggins

WELL NUMBER #2

1650 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 18 TWP. 10 RGE. 19 (X) or (W)

COUNTY Rooks

Date Well Completed 9-27-90

Plugging Commenced 9-27-90

Plugging Completed 9-27-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Calvin Noah

ADDRESS 329 N Birch, Valley Center, KS 67147

PHONE#(316) 755-1032 OPERATORS LICENSE NO. 5616

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-27-90 (date)

by Dale Balthazor (KCC District Agent's Name).

Is ACO-1 filed? Not Yet If not, is well log attached? Yes

Producing Formation D & A Depth to Top \_\_\_\_\_ Bottom T.D. 3814'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		212.4	0	8-5/8	212.4	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged hole with 225 sacks 60/40 Pozmix, 6% gel, 2 sacks Floseal as follows:

25 sx @ 3785', 25 sx @ 1650', 100 sx @ 928', 40 sx @ 240', 10 sx @ 40', 15 sx R.H.,

10 sx M.H. P.D. at 3:45 p.m. 9-27-90.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P.O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Calvin Noah

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Calvin Noah

~~Operator~~ or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Calvin Noah

(Address) 329 N. Birch

Valley Center, KS 67147



AND SWORN TO before me this 16 day of Oct, 1990

(Signature) Shirley Rundell  
Notary Public

My Commission Expires: 9-15-92

15-163-23115-0000

MALLARD JV, INC.  
P.O. BOX 1009  
McPHERSON, KS 67460

DRILLERS' LOG

OPERATOR: CALVIN NOAH  
329 N BIRCH  
VALLEY CENTER, KS 67147

WELL: SCOGGINS #2  
API#: 15-163-23,115

COMMENCED: SEPTEMBER 20, 1990

LOCATION: SE NW SE

COMPLETED: SEPTEMBER 27, 1990

1650 Ft. FSL, 1650 Ft. FEL

TOTAL DEPTH: 3814 Ft.

SEC. 18 TWP. 10 S RGE. 19 W

ELEVATION: 2220 Ft. G.L.

COUNTY: ROOKS

2228 Ft. K.B.

\*\*\*\*\*

STATUS: D & A - Arbuckle Formation

REMARKS:

Cut 12 1/4" hole to 215' and ran 5 joints 8-5/8" x 20# x 202.8' surface casing. Set at 212.4' and cemented with 135 sacks 60/40 Pozmix, 2% gel, 3% cc. Cement did circulate. P.D. at 6:35 p.m. 9-20-90.

Ran 5 DSTs and electric log.

Drilled 7-7/8" hole to 3814' R.T.D. and plugged with 225 sacks 60/40 Pozmix, 6% gel, 2 sacks Floseal as follows:

- 25 sx @ 3785'
- 25 sx @ 1650'
- 100 sx @ 928'
- 40 sx @ 240'
- 10 sx @ 40'

15 sx R.H., 10 sx M.H. P.D. at 3:45 p.m. 9-27-90.

\*\*\*\*\*

STATE OF KANSAS )  
COUNTY OF MCPHERSON ) SS:


I, Dick Hess of MALLARD JV, INC. hereby certify that this is a true and correct copy of the log of the Scoggins #2 well as reflected by the files of Mallard JV, Inc.

RECORDED  
STATE OF KANSAS COMMISSION

*Dick Hess*

OCT 17 1990

Subscribed and sworn to before me this 4th day of October, 1990.



*Bryan K. Hess*  
NOTARY PUBLIC