

RECEIVED

10-24-03

OCT 24 2003

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD KCC WICHITA

K.A.R. 82-3-117

Form CP-4 September 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Bowman Oil Company

Address: 805 Codell Road, Codell, KS 67663

Phone: (785) 434-2286 Operator License #: 6931

Type of Well: oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: Oct 9, 2003 (Date)

by: Dennis Hamel (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Arbuckle Depth to Top: 3790 Bottom: 3795 T.D. 3806

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-163-01953-00-00

Lease Name: Scoggins

Well Number: 4

Spot Location (QQQQ): SW - SE - SW -

330 Feet from North South Section Line

1650 Feet from East West Section Line

Sec. 18 Twp. 10 S. R. 19 East West

County: Rooks

Date Well Completed: May 26, 1949

Plugging Commenced: Oct 9, 2003

Plugging Completed: Oct 9, 2003

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Arbuckle, oil & water, 3790, 3795, 8 5/8, 1636, none. Row 2: 5 1/2, 3830, none.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from feet to feet each set.

Perf well @ 1575, ran tubing to 2700, cemented to surface with 210 sx, tied onto 5 1/2, circulated to surface

(8 5/8 - 5 1/2) w 160 sx, 250 hulls, Shut in pressure 500#

Name of Plugging Contractor: Allied Cementing Co Inc License #:

Address: PO Box 31, Russell, KS 67665


Name of Party Responsible for Plugging Fees: Louis D Bowman for Bowman Oil Company

State of Kansas County, Rooks, ss.

Louis D Bowman (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Louis D Bowman

(Address) 805 Codell Rd, Codell, KS 67663



SUBSCRIBED and SWORN TO before me this 22nd day of October, 2003

Jackie J. Langholz My Commission Expires: 2-24-2005 Notary Public

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


15-163-01953-0000

Company. SKELLY OIL CO.
Farm. L. Scoggins No. 4

SEC. 18 T. 10 R. 19
SW SE SW
990' fr EL, 330' fr SL SW/4

Total Depth. 3830 PB 3797
Comm. 5-14-49 Comp. 5-26-49
Shot or Treated. Acid
Contractor. Herndon Drlg.
Issued. 10-1-49

County. Rocks
KANSAS



Elevation. _____

Production. SCC Pot. 165 bbls.

CASING:

8 5/8" 1636' cem w/625 sx.
5 1/2" 3830' cem w/200 sx.

Figures indicate Bottom of Formations.

surface soil, sand, shale	300
sand, shale	500
shale, shd ls	1000
red bed	1200
shale, shd ls	1360
lime, shells	1629
anhydrite	1640
reamed 9 7/8" hole to 12 1/4"	
anhydrite	1680
red bed	1830
shale, shells	2655
lime, shale	2810
lime	2970
lime, shd ls	3340
lime	3750
lime, chert	3795
dolo. fine to med xlyn.	
	3806
dolo. fine to coarsely xlyn.	
	3830
total depth	
	PB 3797

Tops:	
Anhydrite	1629
Heubner shale	3440
Toronto lime	3462
Lansing lime	3477
Conglomerate	3713
Simpson shale	3779
Arbuckle lime	3795

acid w/300 gals 6-15-49
between 3790-95' by Dowell.

3510-20, fair to good por
light sat.
3531-36, fair por. & sat.
3795-3806, poor to fair por
and sat.
3806-30, poor por. & scattered
stain.

Initial prod. before acid,
15 gal oil in 6 hrs.
Initial prod after acid POB 8 hrs, 55
bbls oil, 1 BW to establish 2 1/2 hr
SCC pot. of 165 bbls.
Producing Formation: Arbuckle lime 3790-95'.

RECEIVED
SEP 08 2003
KCC WICHITA

15-163-01953-0000

ALLIED CEMENTING CO., INC. 14540

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: R

RECEIVED
OCT 24 2003
KCC WICHITA

DATE <u>10/19/03</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>10:00A-M</u>	JOB START	JOB FINISH <u>12:30P-M</u>
LEASE <u>Scops</u>	WELL # <u>4</u>	LOCATION <u>Zurich 3W 4S 1/2 E</u>			COUNTY <u>Rock</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)				<u>NEW</u>			

CONTRACTOR <u>Co Tools</u>	OWNER _____
TYPE OF JOB <u>OH</u>	
HOLE SIZE _____ T.D. _____	CEMENT AMOUNT ORDERED <u>370 100/40 100/60</u>
CASING SIZE <u>5 1/2"</u> DEPTH _____	<u>5 HULLS</u>
TUBING SIZE <u>2"</u> DEPTH _____	<u>USED 370 SF 5 HULLS</u>
DRILL PIPE _____ DEPTH _____	
TOOL _____ DEPTH _____	
PRES. MAX _____ MINIMUM _____	COMMON <u>222</u> @ <u>7.15</u> <u>1587.30</u>
MEAS. LINE _____ SHOE JOINT _____	POZMIX <u>148</u> @ <u>3.80</u> <u>562.40</u>
CEMENT LEFT IN CSG. _____	GEL <u>19</u> @ <u>16.00</u> <u>190.00</u>
PERFS. _____	CHLORIDE _____ @ _____
DISPLACEMENT _____	<u>Hulls 5</u> @ <u>18.00</u> <u>90.00</u>
EQUIPMENT	
PUMP TRUCK CEMENTER <u>Paul</u>	
# <u>177</u> HELPER <u>Shane</u>	HANDLING <u>370</u> @ <u>1.15</u> <u>425.50</u>
BULK TRUCK _____	MILEAGE <u>54/67</u> / MILE <u>647.50</u>
# <u>213</u> DRIVER <u>Cary</u>	(35) TOTAL <u>3502.70</u>
BULK TRUCK _____	
# <u>302</u> DRIVER <u>Scott</u>	

REMARKS:
Tbg @ 2700 Circulate cement
w/ 210 SF. Came out w/ tbg.
5 1/2 csg - Circ cement w/ 1100 SF
and 5 HULLS around 5 1/2 - 8 1/8.
Shut in 8 1/8. Press to 300 psi.
shut in @ 300 psi.

SERVICE

DEPTH OF JOB _____	
PUMP TRUCK CHARGE _____	<u>250.00</u>
EXTRA FOOTAGE _____ @ _____	
MILEAGE _____ @ _____	
PLUG _____ @ _____	
_____ @ _____	
_____ @ _____	
TOTAL _____	<u>250.00</u>

CHARGE TO: Bowman Oil
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____	
_____ @ _____	
_____ @ _____	
_____ @ _____	
_____ @ _____	
TOTAL _____	

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Don Bowman

PRINTED NAME _____

Perf-Tech

Wireline Services, Inc.

P.O. Box 87
HAYS, KS 67601-0087
(785) 623-3969

Invoice

DATE	INVOICE #
10/9/2003	2586

RECEIVED
OCT 24 2003
KCC WICHITA

BILL TO

Bowman Oil Company
101 Petroleum Ave.
Codell Kansas 67630

SERVICE DATE	DESCRIPTION	ITEM	AMOUNT
10/9/2003	Scoggins # 4 Rooks County Kansas		
	Perforated to plug well 2 holes at 1575'	PERF	375.00T
	Truck Rental Sales Tax	Truck set up	350.00T 38.43

Thank you for your business.	Total	\$763.43
------------------------------	--------------	----------