

4-041975

API NO. 15-163-01931000

E-12,298

TO: *5-8*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 1946

C S2 SE NW /4 SEC. 13, 10 S, 19 W  
2310 feet from N section line  
1980 feet from W section line

Operator license# 6113

Lease: H.J. Vohs Well # 7

Operator: Landmark Energy Exploration Inc.

County: Rooks *121.91*

Address: 1861 N. Rock Road #205  
Wichita, Kansas 67206

Well total depth 3751 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 10 3/4 Inch 1484 Feet  
W/550 sxs cmt.

Aband. oil well ; Gas well ; Input well ; SWD ; D & A

Plugging contractor: Express Well Service License# -

Address: Victoria, Kansas 67671

Company to plug at: Hour: 9:00 A.M. Day: 8 Month: May Year 1998

Plugging proposal received from: Allen Walker

Company: Landmark Energy Exploration, Inc. Phone: -

Were: 7" casing set at 3750' w/200 sxs cement. Perfs at 3325' - 3388'.  
Ordered 75 sxs common and 500# hulls.  
Ordered 300 sxs 60/40 pozmix - 10% gel plus 40 sxs gel.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All  , Part  , None

Completed: Hour: 11:00 A.M., Day: 8, Month: May, Year: 1998

Actual plugging report: 5-6-98 bottom plug; R.I.H. with tubing 3300'. Spotted 75 sxs common cement with 500# hulls. 05-07-98 cut-off 7" casing at 1417' and pulled same. 05-08-98 R.I.H. with tubing to 1500'. Spotted 40 sxs gel, followed with 100 sxs cement. Pulled tubing to 825' and spotted 100 sxs cement. Pulled tubing to 200' and spotted 100 sxs cement to circulate at surface. Pulled tubing with cement in cellar.

Remarks:

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO   
Plugged through TUBING  CASING  Elevation: G.L.

I did  / did not  observe the plugging.

*Dennis Hamel*  
(agent)

Form CP-2/3

**INVOICED**

DATE MAY 14 1998

INV. NO. 50559

*5-8* SEP 18 1998

RECEIVED  
5-13-98  
MAY 13 1998  
CONSERVATION DIVISION