

4-071095

4-27 15-163-19389-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 10-13-46

C E2 SW NW /4 SEC. 13, 10 S, 19 W
3300 feet from S section line
4290 feet from E section line

(Track A)

Operator license# 5652

Lease H.J. Vohs B well # 6

Operator: Mustang Oil & Gas Corporation County Rooks

Address: 100 S. Main #300
Wichita, Kansas 67202
Al Hammerschmidt

Well total depth 3586 feet 116.54
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 1458 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing - D.S. & W. License#

Address: Hays, Kansas 67601 - Claflin, Kansas

Company to plug at: Hour: A.M. Day: 27 Month: April Year: 94

Plugging proposal received from: Al Hammerschmidt

Company: Mustang Oil & Gas Corporation Phone: 316-267-8011

Were: 10 3/4" - 1458' S.P. cwc w/550 sxs. 7" casing set at 3584'
w/200 sxs. cement. Elv. 2090' - PBTD 3410' - Anhy. 1480' - Casing good.
D.S. & W. pulled pipe. Proposal sand bottom to 3000' w/7 sxs. cement.
Order 450 sxs. 60/40 pozmix - 10% gel and 5 sxs. hulls. Circulate cement
from 1500' to surface - then cap hole.

Plugging Proposal Received by: Dennis L. Hamel - Herb Deines - Marion Schmidt
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:10 P.M., Day: 27, Month: April, Year: 94

Actual plugging report: Mustang ordered 450 sxs. 60/40 poxmix - 10% gel -
5 sxs. hulls. Plugged hole while pulling casing out of hole. Spotted
and displaced all cement through 7" casing.

- 1) Sanded bottom to 3000' w/8 sxs. cement.
- 2) Shot casing at 1576'.
- 3) 7" casing at 1461' - spotted 160 sxs. cement w/3 sxs hulls.
- 4) 7" casing at 860' - circulated cement out of 7" x 10 3/4" annulus
- 230 sxs. cement. 5) Capped hole to surface w/20 sxs. cement.

Remarks: Allied Cement.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X
Plugged through TUBING , CASING X. Elevation: 2090 GL

I did X / did not observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
MAY 05 1994
CONSERVATION DIVISION
WICHITA, KANSAS
5-5-94

Marion Schmidt
(agent)

INVOICED

MAY 09 1994

DATE

INV. NO. 40397