

3-1215-163-00741-00000 P

6 041145

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 5-24-58

NW SW SE, SEC. 13, T 10 S, R 19 (W/E)

990 feet from S section line

2710 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30152

Lease Name Williams A Well # 1

Operator: Vincent J. Hrabe

County Rooks 120.09

Name & Address Northwestern Supply Co.

Well Total Depth 3695 feet

1111 E. 30th

Conductor Pipe: Size - feet -

Suite 201 Box 1753 Hays, Ks.

Surface Casing: Size 8 5/8 feet 195 w/135 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement License Number

Address Russell, Ks.

Company to plug at: Hour: 9:00AM Day: 12 Month: Mar Year: 19 90

Plugging proposal received from Terry Richardson

(company name) N.W.S. (phone)

were: 4 1/2" casing set at 3693' w/200 sks: Perf at 3350' - 3533: Top of rods at 2000': Top pf tubing at 88': Shot at 1600' and 1300': Perf at 800';

Ordered 100 sks common plus 250 sks 65/35 poz 8% gel w/1/4# f.c.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:00 PM Day: 12 Month: Mar Year: 19 90

ACTUAL PLUGGING REPORT Run in tubing w/overshot to 88'. R.I.H. to

perforate casing/tubing. P.O.O.H. w/perforators. Pull 3 jts of tubing. Hook up to

4 1/2" casing: pumped 100 sks common w/1/4# f.c. followed w/150 sks 65/35 poz w/1/4# f.c.

Max 900# S.I. 600#. Hooked up to 8 5/8" s.p. Pumped in 100 sks 65/35 poz w/1/4# f.c. plus 4 sks hulls in cement. Max 1200# S.I. 600#.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED 5-20-90
DATE 3-26-90
INV. NO. 2770
3-12 JUL 11 1990

Signed Dennis L. Hamel (TECHNICIAN)