

4-14 15-163-19391-0001

6 041035

API NUMBER 15- 2-26-62

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C SE SW, SEC. 13, T 10 S, R 19 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # NA

Lease Name Williams B Well # 1

Operator: Vincent J. Hrabe  
Name & Address: % Northwestern Supply Co.  
Box 1753  
Hays, Ks. 67601

County Rooks 118.24  
Well Total Depth 3638 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 189' w/130 sks

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well  SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_ RT KCC

Plugging Contractor Allied Cement License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: 8:00AM Day: 14 Month: April Year: 19 89

Plugging proposal received from Earl Thomasson

(company name) NW Supply Co. (phone) \_\_\_\_\_

were: 4 1/2" casing set at 3636' w/NA sks. Top perf at 3348'/3460'. Shot at  
1500', 1000', 804', 706', no pipe recovery. Ran w/1 m. 1475'.

Ordered 300 sks 65/35 Poz 8% Gel w/1/4# F.C. plus 8 sks Hulls.

STATE CORPORATION COMMISSION  
5-10-89  
MAY 10 1989  
CONSERVATION DIVISION  
WICHITA, Kansas

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 7:00PM Day: 14 Month: April Year: 19 89

ACTUAL PLUGGING REPORT Pumped in 4 1/2" casing; 50 sks cement w/1/4# F.C.;

released wiper plug - pumped add 200 sks cement w/7 sks Hulls mixed in cement. Max  
1000# Shut in 800# (wiper plug stopped at shot holes at 706' - cmt going by wiper plug  
pumped add. L.C.M. in cement (hurlap pieces); moved plug to next shot holes at 804';  
cement again going by wiper plug. Pressure built to 1000#) hole plugged. Pumped total  
of 95 bbls of slurry in 4 1/2" casing.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-11-89

INV. NO. 24779

4-14

Lib. 3

Signed Dennis L. Hamel  
(TECHNICIAN)  
Dennis Hamel

JUN 12 1989

AUG 08 1989

FEB 12 1990

FORM CP-2/3  
Rev. 01-84