

4-041464

4-28 15-163-19419-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 3-23-63

SE NE NE /4 SEC. 12 , 10 S, 19 W
4290 feet from S section line
990 feet from E section line

Operator license# 5652 Lease Vohs well # 9

Operator: Mustang Oil & Gas Corporation County Rooks

Address: 155 N. Market Well total depth 3795 feet ^{123.33}
Suite #350 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 10 3/4 Inch @ 202 feet
w/150 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mustang Oil & Gas Corporation License# 5652

Address: 155 N. Market - Suite 350 - Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 28 Month: April Year: 93

Plugging proposal received from: Jerry Pritchard

Company: Mustang Oil & Gas Corporation Phone: 316-792-7323

Were: Anhy. @ 1630' cwc. - 625 sxs. Tubing fish left in hole @ 1700'.
Ordered 100 sxs. common with 1/4# F.C. Ordered 300 sxs. 60/40 pozmix -
8% gel. with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:15A.M., Day: 28, Month: April, Year: 93

Actual plugging report: R.I.H. with tubing to 1650'. Spot 100 sx.
common and 265 sx. 60/40 pozmix - 8% gel. to circulate cement to surface.
Pulled tubing and squeezed additional 20 sx. down casing. Max. 300#.
S.I. 300#. Hooked-up to 10 3/4" S.P. Squeezed 15 sxs. cement.
Max. 600#.

Remarks:

Condition of casing(in hole):GOOD BAD X Anhy.plug:YES X NO
Bottom plug(in place):YES X, CALC , NO Dakota plug:YES X NO
Plugged through TUBING X, CASING . Elevation: GL

I did[X]/ did not[] observe the plugging.

Dennis L. Hamel JUN 9 1993

RECEIVED STATE CORPORATION COMMISSION

INVOICES

DATE 6-11-93

WV. NO 37882

(agent) CONSERVATION DIVISION
Wichita, Kansas
Form CP-2/3