

3-29

54R

# 4-060306

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-23,198-0000  
50'N.&100'E.of  
SW SW SE /4 SEC. 13 , 10 S, 19 W  
380 feet from S section line  
2210 feet from E section line

Operator license# 5140 Lease Stepp well # 1

Operator: Frontier Oil Company County Rooks 117.81

Address: 125 N. Market Well total depth 3625 feet  
#1720 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 221 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Red Tiger Drilling Company License# 5302

Address: Wichita, Kansas 67202

Company to plug at: Hour: 6:00P.M. Day: 29 Month: March Year: 92

Plugging proposal received from: Jerry Ogle

Company: Red Tiger Drilling Company Phone: 316-263-1201

Were: Order 215 sks. 60/40 posmix - 6% gel - 1/4# flocele per sx.  
Space all plugs with heavy drilling and through drill pipe.


Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 6:00P.M., Day: 29, Month: March, Year: 92

Actual plugging report:

<u>1st. plug at 3614' with 25 sxs.</u>	<b>RECEIVED</b>
<u>2nd. plug at 1490' with 25 sxs. - Anhydrite 1470' - 1501'</u>	STATE CORPORATION COMMISSION
<u>3rd. plug at 820' with 100 sxs. - Dakota 517' - 817'.</u>	4-9-92
<u>4th. plug at 275' with 40 sxs. - Surface pipe to 221'.</u>	APR 09 1992
<u>5th. plug at 40' with 10 sxs.</u>	
<u>Rathole with 15 sxs.</u>	CONSERVATION DIVISION Wichita, Kansas

Remarks: Allied Cementing.  
Condition of casing(in hole):GOOD  BAD  Anhy.plug:YES  NO   
Bottom plug(in place):YES  , CALC  , NO  Dakota plug:YES  , NO   
Plugged through TUBING  , CASING  . Elevation: 2092 GL

I did  / did not  observe the plugging. 

DATE 4-22-92  
INV NO. 34977

*Herb S*

(agent)  
Form CP-2/3