

4- 041389

7-27  
15-163-03705-0000/2  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 2-18-46

NE SE NE /4 SEC. 14, 10 S, 19 W  
3630 feet from S section line  
330 feet from E section line

Operator license# 5652

Lease Vohs well # 3

Operator: Mustang Oil & Gas Corp.

County Rooks

117.39

Address: 155 N. Market  
Suite 350  
Wichita, Kansas 67202

Well total depth 3612 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 1440 feet  
w/700 sx.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00A.M. Day: 27 Month: July Year: 92

Plugging proposal received from: Jerry Pritchard

Company: Mustang Oil & Gas Corp. Phone: 316-792-7323

Were: 5 1/2" casing set @ 3510' w/200 sx. cement. B.P. @ 3155'.  
Perf. @ 1450'. Ordered 525 sx. 60/40 pozmix - 8% gel. with 1/4# F.C.  
plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 4:00P.M., Day: 27, Month: July, Year: 92

Actual plugging report: Hooked-up to 8 5/8" annulus. Pressured-up  
600#. Ran in hole with tubing to 3155'. Spot 120 sx. cement to 1410'.  
Pull up tubing to 1410'. Run in hole with perf. to perf. @ 1450'.  
Spot cement @ 1410' to surface (inside and outside casing) cement  
circulate. P.O.O.H. with tubing, squeeze casing and annulus to 500#  
with a shut-in of 300#. Used a total of 325 sx. of 60/40 pozmix 10%  
gel.

Remarks:

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X  
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X  
Plugged through TUBING X, CASING    . Elevation:     GL    

I did X did not [     ] observe the plugging.

Dennis L. Hamel

INVOICED  
DATE 8-20-92  
REV. NO. 35997

(agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1992  
8-10-92  
CONSERVATION DIVISION  
WICHITA, KANSAS