

8-27

6 070857

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-00259-0000
NE NE NE , SEC. 14, T 10, S, R 19 W/E xx

4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652
Operator: Mustang Drilling Inc. COMPANIES, INC.
Name & Address: South Hwy 281 Box 1609
Great Bend, Ks. 67530
J. P. Meroney

Lease Name Vohs Well # 1
County Rooks 116.93
Well Total Depth 3598 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 1227

Abandoned Oil Well xx Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing and Express Well Service License Number

Address Russell, Ks. Victoria, Ks.

Company to plug at: Hour: AM Day: 27 Month: August Year: 19 90

Plugging proposal received from Jim Meroney

(company name) Mustang Drilling Inc. (phone) 316-792-6877

were: 13 3/8 115 ft. cond w/100 sks cement cir. 8 5/8 1227 ft. s.p. cwc w/350 sks cement
5 1/2 casing set at 3549 ft. w/100 sks cement- 5 1/2 casing. Sq at 1767 and 2047 w/150 sks cement
CIBP at 3100. Proposal 375 sks 65/35 poz 8% gel and 5 sks hulls. Perf at 1420. Run
tubing to 3050. Spot and displace 150 sks cement w/4 sks hulls mixed in. Pull tubing
to 1170. circ w/ cement out of 5 1/2 casing. Pressure 5 1/2 x 8 5/8 annulus with cement.
Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 3:00 PM Day: 27 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Mustang ordered 375 sks 65/35 poz

8% gel and 5 sks hulls. 1. Ran 2 7/8 tubing to 3050. Spotted and displaced 150 sks
cement w/4 1/2 sks hulls added. 2. 2 7/8 tubing at 1170 circ cement out of 5 1/2 casing w/
90 sks cement. 3. Sq annulus with cement. 1100 psig. Max Shut in at 1100 psig. Did
not take cement. Sq 5 1/2 casing w/100 sks. Max pressure 600 psig. Shut in at 300 psig.
Allied Cement Co.

Remarks: L. K. Wireline perforated 5 1/2 casing at 1420.
(If additional description is necessary, use BACK of

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS

SEP 10 1990
9-10-90

INVOICED

SEP 18 1990

DATE: SEP 18 1990

INV. NO. 29344

8-27

Handwritten initials

Signed Marion J. Schmidt (TECHNICIAN)