

12-23  
4-060485

15-163-01936-0002

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 9-8-45

SW NE NE /4 SEC. 14, 10 S, 19 W  
4290 feet from S section line  
990 feet from E section line

Operator license# 5652 Lease Vohs well # 2

Operator: Mustang Oil & Gas Corporation County Rooks

Address: 100 S. Main Well total depth 3563 feet 115.80  
Suite #300 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 1165 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 12:00 P.M Day: 23 Month: December Year: 93

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 325 sxs. 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 4:15 P.M., Day: 23, Month: December, Year: 93

Actual plugging report: 8 5/8" to 1165' with 400 sxs. 5 1/2" to 3563'  
with 200 sxs. Sanded to 3220' and spotted 5 sxs. cement with dump bailer.  
Casing parted in anhydrite. Pumped 105 sxs. cement with 200# hulls.  
Pulled casing to 700' and pumped 50 sxs. cement with 100# hulls. Pulled  
casing to 350' and pumped 70 sxs. cement. Pulled casing and tied onto  
surface pipe. Mixed and pumped 105 sxs. cement with 100# hulls.  
Max. 150#. S.I.P. 50#. Used 330 sxs. cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO    

Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO    

Plugged through TUBING    , CASING X. Elevation: 2057 GL    

I did X did not     observe the plugging.

INVOICED  
DATE 1-7-94  
INV. NO. 39646

    (agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
1-30-94  
JAN 03 1994  
CONSERVATION DIVISION  
Wichita, Kansas