

1-23 (15-163-00417-0000) 9  
R

6 - 070983

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- 6-28-52

NW NE SW /4 SEC. 16, 10 S. 19 W  
2310 feet from S section line  
3630 ~~4950~~ feet from E section line

Operator license# 6568 Lease Fehnel well # 1

Operator: Kaiser Francis Oil County Rooks

Address: Box 21468 Well total depth 3227 feet  
Tulsa, OK 74121-1468 Conductor Pipe:      inch @      feet  
Surface pipe 8 5/8 inch @      feet

Aband. oil well xx, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: B. J. Services License#     

Address: Hays, Ks. 67601

Company to plug at: Hour: AM Day: 23 Month: Jan Year: 92

Plugging proposal received from: John Glenn

Company: Kaiser Francis phone: 918-494-000

Were: 8 5/8 167 ft. s.p. cwc w/100 sks. 5 1/2 casing set at 3727 ft  
w/150 sks cement. Perfs 3436 - 3578. Casing squeezed at 928 and 915  
to 2570 w/n.a. Proposal 400 sks 60/40 poz 8% gel and 5 sks cement  
Pump in w/pump truck. Run 2 3/8 tubing to a min. of 3000 ft. Spot  
and displace cement. Load both casing and 5 1/2 x 8 5/8 annulus w/cmt.

Plugging Proposal Received by:       
Plugging operations attended by agent? All [ x ], Part [      ]

Completed: Hour: 2:30PM, Day: 23, Month: January, Year: 1992

Actual plugging report: Kaiser Francis ordered 400 sks  
60/40 poz 8% gel and 5 sks hulls pumped in w/pump truck. Loaded both  
5 1/2 casing and 5 1/2 x 8 5/8 annulus. 1. 2 3/8 tubing at 3310 w/  
15 sks cement followed w/85 sks cement w/3 sks hulls added. 2. 2 3/8  
tubing at 1820 ft w/150 sks cement, cement circ out of 5 1/2 casing.  
3. Squeezed annulus w/0 cement 750 psig. Max shut in at 750 psig.  
Cemented by B. J. Services.

Remarks:       
Condition of casing (in hole): GOOD x BAD      Anhy. plug: YES x NO       
Bottom plug (in place): YES x, CALC     , NO      Dakota plug: YES     , NO       
Plugged through TUBING x, CASING      Elevation:      GL

[ did ] / [ did not ] observe the plugging.

INVOICED

*Marion J. Schmidt*  
Marion J. Schmidt (agent)  
Form CP-213

DATE 2-17-92  
INV. NO. 34576

*John S.*