

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 148-22

LOCATION SW-SW-SW

SEC. 13 TWP. 16 RGE. 19-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Hennie

Operator Norby & Bohm, Inc. Address 2603 Philtown, Bldg-Tulsa-Okla

Field _____ County Nowata

Total Depth 3607 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 1434 ft. Circulated with Cement
5 1/2" casing set at 3600 ft. cemented & well tested in
14 City Time - 26 Oil - Plugged back from bottom to 3300 ft.
5 sacks of cement at 3300 ft. - Shot off & recovered 2800 ft
of 5 1/2" casing - Filled with mud to 1435 ft. - 10 sacks cement
at 1435 ft. - Mud to 200 ft Plug & 10 sacks cement at 200 ft.
Mud to within 20 ft of the surface - Plug & 10 sacks cement.

Carl Miller
Pipe Puller & Plugger

C. M. Stough
District Conservation Agent

Date 1-15-48

PLUGGING
FILE SEC 13 T 16 R 19W
BOOK PAGE 148 LINE 22

