

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Dave Collins Universal Well Service

Complete Address 300 S. Wyoming Plainville, Kansas 67663

Lease Name ~~H. J. Vohys~~ Vohs 'G' Well No. 1

Location C ~~NW SW NE~~ NW NE ^{BT REC} Sec. 12 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3775

Abandoned Oil Well XXX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 4:30P Day 14 Month 1 Year 1971

The above well was plugged as follows:

Total Depth 3775' 8 5/8 csg set at 172' cwc 115 sk.

1 1/2 csg set at 3755' cw 150 sk cmt.

1 1/2 csg PBTB 3512' with top perf. (3441'0)

Filled 1 1/2 csg W/sd (3425-3512) Dumped 4 sk cmt W/dump bailer. (3390-3425)

Recovered 706' of 1 1/2 csg.

Pumped down 8 5/8 csg with 21 sk gel W/5 sk hulls - Surface pipe circ - could not sq.

Washed 2" tubing to 350' circ 7 sk gel and 120 sk poz 6% to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bo F. Massey
Well Plugging Supervisor

DATE 1/18/71
INV. NO. 3220-W