

15-163-01932-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-4-70
SEP 4 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kewanee Oil Company

Complete Address P. O. Box 360 Hoisington, Kansas 67514

Lease Name Catuda "A" Well No. 1

Location NE NW NE Sec. 11 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3601

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 10:30A Day 3 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 3601' 8 5/8 csg set at 1445' cwc 700 sk.

5 1/2 csg set at 3593' cw 200 sk cmt.

5 1/2 csg perf. (3186-3191)

Filled 5 1/2 csg W/sd (3580-3601) Dumped 4 sk cmt W/dump bailer. (3550-3580)

Set wood plug (5 1/2) at 3175' poured sd and 4 sk cmt W/dump bailer. (3130-3175)

Cutoff and recovered 2520' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 740' - set rock bridge and dumped 3 yds RMC (500-740)

Filled with mud to 240' - set rock bridge and 3 yds RMC (0-240)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. F. Massey
Well Plugging Supervisor

DATE 9-4-70

INV. NO. 2479-W