

15-163-03704-0000

Form CP-3
Rev. 6-26-62

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kewanee Oil Company

Complete Address: Box 360 Hosington, Kansas 67544

Lease Name Catudal "B" Well No. 1

Location NE NE NW Sec. 14 Twp. 10 Rge. 19 (E) (W) X

County Rooks Total Depth 3643

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364 Great Bend, Ks. License No. 399

Operation Completed: Hour 4 P Day 15 Month 3 Year 1968

The Above well was plugged as follows:

Total Depth 3643' 8 5/8 csg set at 1480' cwc 700 sc.

5 1/2 csg set at 3639' cw 200 sc cement.

5 1/2 PBTD 3395' with top perf. at 3094'

Pushed plug to 3050' Poured 25' sand and dumped 5 sc cement with dump bailer.

Recov. 2514' of 5 1/2 csg.

Mud to 720' set 25' rock bridge and 20 sc cement plug.

Mud to 275' set 25' rock bridge and 20 sc cement plug.

Mud to 65' set 25' rock bridge and 10 sc cement plug to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/18/68
INV. NO. 4441-W

Signed: [Signature]
Well Plugging Supervisor