

15-163-01934-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

9-18-70
RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kewanee Oil Company Wichita, Kansas

Complete Address P. O. Box 360 Hoisington, Kansas 67514

Lease Name Catual "A" Well No. 3

Location C S/2 NW NE Sec. 14 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3626

Abandoned Oil Well XXX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 11 A Day 17 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 3626' 8 5/8 csg set at 1463' cwc 750 sk.

5 1/2 csg set at 3621' cw 200 sk cmt.

5 1/2 csg perf. (3206)

Filled 5 1/2 csg W/sd (3600-3626) Dumped 1/2 sk cmt W/dump bailer. (3560-3600)

Set 5 1/2 wood plug at 3150' -poured 10' sd -dumped 1/2 sk cmt W/dump bailer. (3100-3150)

Cutoff and recovered 2589' of 5 1/2 csg.

Filled 8 1/2 5/8 csg with mud to 720' -set 20' rock & 3 yds readymix cmt to 480'.

Mud to 235' -set 15' rock & 3 yds readymix cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-18-70

INV. NO. 2553-W

Signed: Leo J. Massey
Well Plugging Supervisor