

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 3-42

LOCATION SW-SE-SE

SEC. 14 TWP. 10 RGE. 19-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1-B Lease Vohs

Operator Norby & Bothwell-Drillers Address 2003-Philtower Bldg-Tulsa-Okla

Field _____ County Nooks

Total Depth 3575 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 1421 ft. Circulated with Cement
5 1/2" casing set at 3575 ft. cemented & Well Tested - No Oil
Plugged back from bottom to 3250 - Put in 5 sacks of
Cement in 5 1/2" casing with Manns Bailor - Shot off & removed
2900 ft of 5 1/2" casing - filled with mud to 1420 ft. Then
15 sacks cement - Mud to 200 ft. Plug + 10 sacks cement
Surface Plug 20 ft below the surface & 5 sacks of cement.

Carl Miller
Pipe Puller & Plugger

C. N. Stough
District Conservation Agent

Date 1-12-48

PLUGGING
FILE SEC 14 T 10 R 19W
BOOK PAGE 3 LINE 42