

KANSAS

f STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address Box 18412 Wichita, Kansas 67218

Lease Name Sutor Well No. 1

Location W/2 SW SW Sec. 11 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3720'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 6:15 P Day 16 Month 1 Year 1970

The above well was plugged as follows:

RTD 3720' 8 5/8 csg set at 249' cwc 185 sk. Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 850' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 275' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Messer
Well Plugging Supervisor

INVOICED

DATE 1/18/71
INV. NO. 3232-W